

**Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)**

**Submission Title:** [LOS residential channel model based on TSV model]

**Date Submitted:** [September, 2006]

**Source:** [Hirokazu Sawada, Yozo Shoji, Chang-Soon Choi, Katsuyoshi Sato, Ryuhei Funada, Hiroshi Harada, Shuzo Kato, Masahiro Umehira, and Hiroyo Ogawa]

Company [National Institute of Information and Communications Technology]

Address [3-4, Hikarino-Oka, Yokosuka, Kanagawa, 239-0847, Japan]

Voice:[+81.46.847.5096], FAX: [+81.46.847.5079], E-Mail:[sawahiro@nict.go.jp]

**Re:** []

**Abstract:** [This contribution describes LOS residential channel model based on TSV model.]

**Purpose:** [Contribution to mmW TG3c meeting.]

**Notice:** This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

**Release:** The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

# LOS residential channel-model based on TSV model

Hirokazu Sawada, Yozo Shoji, Chang-Soon Choi,  
Katsuyoshi Sato, Ryuhei Funada, Hiroshi Harada,  
Shuzo Kato, Masahiro Umehira, and Hiroyo Ogawa

National Institute of Information and  
Communication Technology (NICT), Japan

## Agenda

- Background
- Measurement procedure and results
- Extracted TSV model parameters

## Background

- Channel model for LOS residential environment was released. However the parameter for only omni antenna is available

## Purpose

- Re-analyzing LOS residential data (provided by NICT) based on TSV model, and extracting the parameters for all directional antennas

## Measurement conditions (06/012)

Instrument	HP8510C VNA
Center frequency	62.5 GHz
Bandwidth	3 GHz
Time resolution	0.333 ns
Distance resolution	19.1 cm
# of frequency points	401
Frequency step	7.5MHz
Times of average	128 times

Time resolution and distance resolution were determined by bandwidth

## Measurement conditions (cont')

- Pyramidal horn antennas
- Omni directional antenna
- Calibration performed with 1m reference separation




Omni directional




Pyramidal horn

# Measurement environment



## Floor plan of home environment

## Measurement environment (cont')



Antenna height : 1.1m



## TSV model for LOS residential environment

- For LOS desktop environment (06/297)

TSV model = Statistical two-path component + S-V components

$$h(t) = \beta \delta(t) + \sum_{l=0}^{L-1} \sum_{m=0}^{M_l-1} \alpha_{l,m} \delta(t - T_l - \tau_{l,m}) \delta(\varphi - \Psi_l - \psi_{l,m})$$

$$\beta = \sqrt{PL} \left( \frac{\mu_D}{D} \right)^2 \left| \sqrt{G_{t1} G_{r1}} + \sqrt{G_{t2} G_{r2}} \Gamma_0 \exp \left[ j \frac{2\pi}{\lambda_f} \frac{2h_1 h_2}{D} \right] \right|$$

Statistical factors in both two-path and S-V

*PL*: Path loss

- For LOS residential environment

Reflection coefficient:  $\Gamma_0 \doteq 0$

Modified TSV model = Direct-path component + S-V components


$$h(t) = \beta \delta(t) + \sum_{l=0}^{L-1} \sum_{m=0}^{M_l-1} \alpha_{l,m} \delta(t - T_l - \tau_{l,m}) \delta(\varphi - \Psi_l - \psi_{l,m})$$

$$\beta \Big|_{\mu_D \ll D} = \sqrt{PL G_{t1} G_{r1}}$$

Statistical factors in only S-V

*Refer to Appendix A for each parameter*

## Impulse response



By setting  $\Gamma_0 = 0$ , TSV model can generate impulse response for LOS residential channel without any modification


## Extracted TSV model parameters

Parameter	TSV Model $\Omega_0(\text{D})@3\text{m}$ [dB]	Small Rician effect k ( $\Delta k$ )	S-V model oriented parameter							Number of cluster N
			$\Gamma$ [ns]	$1/\Lambda$ [ns]	$\gamma$ [ns]	$1/\lambda$ [ns]	$\sigma_1$ cluster	$\sigma_2$ ray	$\sigma_\phi$ [deg]	
Tx:360 Rx:15	-88.7	4.34 (18.8 dB)	4.46	5.24	6.25	0.820	6.28	13.0	49.8	9
Tx:60 Rx:15	-108	4.00 (17.4 dB)	8.98	5.15	9.17	1.11	6.63	9.83	119	11
Tx:30 Rx:15	-111	2.73 (11.9 dB)	21.5	6.94	4.35	0.856	3.71	7.31	46.2	8
Tx:15 Rx:15	-110.7	1.06 (4.60 dB)	12.6	22.2	4.98	1.08	7.34	6.11	107	4

Channel model for LOS residential environment was reanalyzed

Refer to Appendix B for each parameter

## Measurement of Path loss in LOS residential environment



- No rotational measurement, only path loss in LOS direct component was measured

## Path loss of LOS component in residential environment

$$\text{Path loss [dB]} = PL_0 + 10n \log_{10}(\mu_D / D_0)$$




Fig. Path Loss result

- Path loss at  $D_0=1\text{m}$  distance

$$PL_0[\text{dB}] = 20 \log_{10} \left( \frac{4\pi D_0}{\lambda} \right) \approx 68.4$$

$$\lambda \approx 4.8\text{mm} \quad (f = 62.5\text{GHz})$$

- Path loss exponent

$$n = 2.06$$

- Path loss of LOS component follows free space loss

## Summary of available LOS / NLOS channel models

	LOS	NLOS
Office	Available (NICT)	Available (NICTA)
Residential	Available (NICT)	N/A
Desktop	Available (NICT)	N/A
Library	Available (IMST/Intel)	N/A

These parts are now available based on TSV-model

## Summary

- The parameters for LOS residential channel model was re-reanalyzed based on TSV-model
- Path loss for LOS residential environment was clarified
- Channel model and Path loss model for LOS residential environment is now available
- Channel models for LOS environments (residential, office, desktop) based on TSV model are now available

# Appendix A: Definition of TSV model (modified)

**CIR:** 
$$h(t) = \beta \delta(t) + \sum_{l=0}^{L-1} \sum_{m=0}^{M_l-1} \alpha_{l,m} \delta(t - T_l - \tau_{l,m}) \delta(\varphi - \Psi_l - \psi_{l,m})$$

(Complex impulse response)

$$|\alpha_{l,m}|^2 = \Omega_0 e^{-T_l/\Gamma} e^{-\tau_{l,m}/\gamma - k[1-\delta(m)]} \sqrt{G_r(0, \Psi_l + \psi_{l,m})}, \angle \alpha_{l,m} \propto \text{Uniform}[0, 2\pi)$$

*PL: Path loss of the first impulse response*

*t: time[ns]*

*$\delta(\cdot)$ : Delta function*

*l = cluster number,*

*m = ray number in l-th cluster,*

*L = total number of clusters;*

*$M_l$  = total number of rays in the l-th cluster;*

*$T_l$  = arrival time of the first ray of*

*the l-th cluster;*

*$\tau_{l,m}$  = delay of the m-th ray within the l-th cluster*

*relative to the first path arrival time,  $T_l$ ;*

*$\Omega_0$  = Average power of the first ray of the first cluster*

*$\Psi_l \propto \text{Uniform}[0, 2\pi)$ ; arrival angle of the first ray within the l-th cluster*

*$\psi_{l,m}$  = arrival angle of the m-th ray within the l-th cluster relative to the first path arrival angle,  $\Psi_l$*

## Two-path response

$$\beta = \sqrt{PL} \left( \frac{\mu_D}{D} \right)^2 \left| \sqrt{G_{r1} G_{r1}} + \sqrt{G_{r2} G_{r2}} \Gamma_0 \exp \left[ j \frac{2\pi}{\lambda_f} \frac{2h_1 h_2}{D} \right] \right|$$

Path number of  $G_{ri}$  and  $G_{ri}$  (1 : direct, 2 : reflect)

## Arrival rate: Poisson process

$$p(T_l | T_{l-1}) = \Lambda \exp[-\Lambda(T_l - T_{l-1})], \quad l > 0$$

$$p(\tau_l | \tau_{l,(m-1)}) = \lambda \exp[-\lambda(\tau_l - \tau_{l,(m-1)})], \quad m > 0$$

## Two-path parameters (4)

$D \propto \text{Uniform}$  : Distance between Tx and Rx

$h_1 \propto \text{Uniform}$  : Height of Tx

$h_2 \propto \text{Uniform}$  : Height of Rx

$\mu_D \propto \text{Average}$  of distance between Tx and Rx

$|\Gamma_0|$  : Reflection coefficient

$|\Gamma_0| \cong 1$  : LOS Desktop environment  
(incident angle  $\cong \pi/2$ )

$|\Gamma_0| \cong 0$  : Other LOS environment

## S-V parameters (7)

$\Gamma$  : cluster decay factor

$1/\Lambda$  : cluster arrival rate

$\gamma$  : ray decay factor

$1/\lambda$  : ray arrival rate

$\sigma_1$  : cluster lognormal standard deviation

$\sigma_2$  : ray lognormal standard deviation

$\sigma_\phi$  : Angle spread of ray within cluster

(Laplace distribution)

## Antenna parameters (2)

$G_t(\theta, \phi)$  : Antenna gain of Tx

$G_r(\theta, \iota)$  : Antenna gain of Rx

## Rician factor (2)


$k$  : Small Rician effect in each cluster

$$K = \frac{\beta^2}{\sum_{l=0}^{L-1} \sum_{m=0}^{M_l-1} |\alpha_{l,m}|^2 \delta(t - T_l - \tau_{l,m}) \delta(\varphi - \Psi_l - \psi_{l,m}) G_r(0, \Psi_l + \psi_{l,m})}$$




# Appendix B: Results of data analysis


Antenna beamwidth  
Tx: 360 deg, Rx: 15 deg




Cluster decay factor ( $\Gamma$ )




Cluster arrival rate ( $1/\Lambda$ )




Ray decay factor ( $\gamma$ )




Ray arrival rate ( $1/\lambda$ )




Angle of arrival in cluster ( $\propto$  Uniform)



Angle spread of ray ( $\sigma_\phi$ )



Standard deviation of cluster ( $\sigma_1$ )



Standard deviation of ray ( $\sigma_2$ )