Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: [Proposed antenna reference models for each Usage Model Definition]

Date Submitted: [October, 2006]

Source: [Hirokazu Sawada, Yozo Shoji, Chang-Soon Choi, Katsuyoshi Sato, Ryuhei Funada,

Hiroshi Harada, Shuzo Kato, Masahiro Umehira]

Company [National Institute of Information and Communications Technology]

Address [3-4, Hikarino-Oka, Yokosuka, Kanagawa, 239-0847, Japan]

Voice:[+81.46.847.5096], FAX: [+81.46.847.5079], E-Mail:[sawahiro@nict.go.jp]

Re: []

Abstract: [This contribution describes antenna reference model for each Usage Model Definition]

Purpose: [Contribution to mmW TG3c meeting.]

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Proposed antenna reference models for each Usage Model Definition


Hirokazu Sawada, Yozo Shoji, Chang-Soon Choi, Katsuyoshi Sato, Ryuhei Funada, Hiroshi Harada, Shuzo Kato, Masahiro Umerhira

National Institute of Information and Communication Technology (NICT), Japan

Basic reference antenna model


Antenna gain: $G_r(\theta, \phi) = GD(\theta, \phi)$

- Omni directional antenna: $D(0, \phi) = 1$
- Directional antenna: $D(0, \phi) = \exp(-\alpha \phi^2)$



of beam-width

Fitting results of antenna patterns



Gaussian distribution well agree with actual antenna pattern

Proposed reference parameters for each UMD

	Devices	Antenna	Correspondent	Maximum	Form	Bandwidth
		beam-width	3-dB beam-width	antenna gain	factor	[GHz]
		factor (\alpha)	[deg]	[dBi]	[mm] ※ 1	
UM1	TV	40	15	22	20×40	
	STB	40	15	22	20×40	
UM2	TV	40	15	22	20×40	
	STB	40	15	22	20×40	16
UM3	PC	2.5	60	10	4×1	[59-75 GHz]
	Peripheral	2.5	60	10	4 × 1	
	TV	40	15	22	20×40	
UM4	PC	2.5	60	10	4 × 1	
	Wireless bridge	2.5	60	10	4 × 1	
	TV	40	15	22	20×40	
UM5	Server(STB)	2.5	60	10	4×1	
	PDA	10	30	16	10×10	

※1: Conical horn antenna: Diameter

★ Length

Policy used in selecting antenna parameters

- The reference antenna should be selected from the antennas used to create the channel model
- The same type of device is assumed to use the same type antenna over all usage models
- The antenna beam width should be practically reasonable

Appendix: Conical horn antennas



These antennas were used in channel measurement