January 2008

#### <u>doc.: IEEE 802.15-<08/0052-00></u>

#### **Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)**

Submission Title: [Visible Light communications: A European perspective]

Date Submitted: [15 January 2008]

Source: [(1) Dominic O'Brien, Hoa Le Minh (2) Olivier Bouchet (3) Sebastian Randel,,

Joachim Walewski (4) Klaus-Dieter Langer, Jelena Grubor (5) Jose A. Rabadan Borges, Rafael Perez Jimenez]

Company [(1) University of Oxford (2) France Telecom (3) Siemens Corporate Technology, Information and

Communications (4) Fraunhofer, Heinrich-Hertz-Institute (5) ETSIT Universidad de Las Palmas de Gran Canaria] Address []

Voice:[], FAX: [], E-Mail:[(1) dominic.obrien@eng.ox.ac.uk, Hoa.le-minh@eng.ox.ac.uk (2) olivier.bouchet@orange-ftgroup.com (3) sebastian.randel@siemens.com (4) langer@hhi.fraunhofer.de, grubor@hhi.fraunhofer.de (5) jrabadan@dsc.ulpgc.es, rperez@dsc.ulpgc.es]

**Re:** []

**Abstract:** [VLC offers capacity augmentation in simple broadcasting and potential for very high speed optical links over short distance. It features small cell sizes, intuitive security, and intuitive pointing.]

**Purpose:** [Contribution to IEEE 802.15 IG-VLC]

**Notice:** This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

**Release:** The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

# Visible Light communications: A Europe an perspective

Dominic O'Brien, University of Oxford, dominic.obrien@eng.ox.ac.uk

Hoa Le Minh, University of Oxford, Hoa.le-minh@eng.ox.ac.uk

Olivier Bouchet, France Telecom, olivier.bouchet@orange-ftgroup.com

Sebastian Randel, Siemens Corporate Technology, Information and Communications, sebastian.randel@siemens.com

Joachim Walewski, Siemens Corporate Technology, Information and Communications, joachim.walewski@siemens.com

Klaus-Dieter Langer, Fraunhofer, Heinrich-Hertz-Institute, langer@hhi.fraunhofer.de

Jelena Grubor, Fraunhofer, Heinrich-Hertz-Institute, grubor@hhi.fraunhofer.de

Jose A. Rabadan Borges, ETSIT Universidad de Las Palmas de Gran Canaria, jrabadan@dsc.ulpgc.es

Rafael Perez Jimenez, ETSIT Universidad de Las Palmas de Gran Canaria, rperez@dsc.ulpgc.es

# Overview

- Introduction
- Technical overview
- Research in Europe
- VLC community
- Future developments

# Introduction: the lighting landscape


- Domestic
  - Mostly incandescent/compact fluorescent
  - Some LED lamps available
  - 18 TWh/annum used in UK [1]
    - Potential for 3TWh/annum with total conversion to 100 lumen/W LED
- Commercial
  - Fluorescent, and vapour lamps (48TWh/annum in the UK)
    - Increasing interest in sensor-based control
      - DALI (digital addressable lighting interface) bus used to communicate between sensors and dimming ballasts
      - Wireless networks using Zigbee etc. to control lights, with possibility of self-power

[1] 'Light emitting diodes: eco-design innovation roadmap', UK Market Transformation


Programme,2005, available for download from www.mtprog.com

# Technical overview: sources

- Two types of LED
  - RGB triplet devices
  - Single chip+ phosphor devices
- Typically driven with several 100mA at 2.5-3V, producing 100mW optical power




### Technical overview: sources




Measurements from the University of Oxford

## Technical overview: channel



# Technical overview: Channel

- Two propagation paths
  - Line of sight
    - Strong paths calculated using the illumination patterns from LED arrays
  - Diffuse
    - Modelled by assuming the room is equivalent to an integrating sphere
- Channel impulse response calculated for each point in the room




Typical impulse response


Submission

## Technical overview: Receiver


- Receiver

   Optical filter
   Rejects 'out-of-band' ambient illumination noise
   Removes slow yellow component
  - Lens system or concentrator
    - Collects and focuses radiation
  - Photodetector (or array of detectors)
    - Converts optical *power* to *photocurrent* Incoherent detection
  - Preamplifier
    - Determines system noise performance
  - Post-amplifier and subsequent processing





Data rate 33Mb/s




# Attributes of VLC

- Security
- Low complexity
- Aesthetics
- Potential of short range 'point and shoot'
- Immunity to RF electro-magnetic interference (EMI)
- Directivity and an intrinsically small cell size (femtoc ells, shielding by opaque surfaces) offering spatial r euse opportunities
- High SNR due to high lighting level
- Dual use of lighting ("zero"-CAPEX & -OPEX data tr ansmission as compared to lighting-only scenarios)
- No e-smog

## Systems results

- Data rate
  - 40Mb/s NRZ over very short distances (Fraunhofer, Heinrich-Hertz-Insitute)
    - 20MHz bandwidth
    - Implies 100Mb/s DMT
    - Simulations show feasible over longer ranges in typical lighting scenarios
  - ~40Mb/s over several metres (University of Oxfo rd)
- Broadcasting
  - CD broadcast using 5-6Mb/s VLC link (University of Oxford)

#### Music broadcast demonstrator



Transmitter

Music demonstrator fabricated at University of Oxford

# VLC: European research

- Growing interest in Europe
  - Groups including
    - Siemens, Fraunhofer, Heinrich Hertz Institute, University of Las Palmas de Gran Canaria, France Telecom, University of Oxford
  - Completed EU project 'ISLE' with car to car communications usin g LED lamps
  - EU project 'OMEGA' with Optical Wireless communications under way
- Wireless World Research Forum
  - Working towards VLC whitepaper (completion in April 2008)
  - Possible book on VLC
    - Contributions solicited, particularly from solid state lighting industry
    - (email dominic.obrien@eng.ox.ac.uk)

# Challenges: Technical

- Modulation bandwidth
  - DMT (requires linear LED drivers)
  - Modification of device structure
  - Link equalisation
- PWM illumination control
  - Gaps in transmission waveform
  - Noisy electrical waveform from DC converter circuitry
- Provision of an uplink
  - Cooperative optical and RF wireless
- Provision of higher network layers
  - Little work as yet


## Challenges: standardisation

- Need to consider other standards
  - Illumination
    - Levels, control mechanisms
    - PLC etc
- Advantage
  - New field and not so many 'vested interests'

#### Possible targets for standardisation

- Local broadcasting
  - Unidirectional
  - Demonstrations and simulations of 40Mb/s NRZ (100Mb/s with high processing)
  - Digital TV multiplex (several)
  - Radio spectrum resource saved for bidirectional shared chan nel communications
- Very high speed data links
  - Visibility offers easy alignment and better link budget
  - Sub 1 metre could be more efficient than UWB and/or IRDA

### Possible broadcasting scenario



# Conclusions

- VLC offers
  - Capacity augmentation and simple broadcasting
  - Potential for very high speed optical links over short distance
  - small cell sizes
  - intuitive security
  - intuitive pointing
- Next steps
  - Representatives of lighting community
  - System designs
    - VLC broadcast
      - Progress in link data rates
    - High-speed link
      - Basic work still required for good comparison with other technologies