#### Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

**Submission Title:** [Coexistence of UWB-BANs with other Wireless Systems ]

Date Submitted: [21 January 2009]

Source: [Marco Hernandez, Ryuji Kohno] Company: [NICT]

Address: [3-4 Hikarino-oka, Yokosuka, 239-0847, Japan]

Voice: [+81 468475439] Fax: [+81 468475431] Email: [Marco@nict.go.jp]

**Re:** []

**Abstract:** [The presentation shows some preliminary results on the coexistence of UWB-BAN devices with other wireless systems.]

**Purpose:** [Identifying when UWB-devices represent a serious degradation in performance sensitivity of other wireless systems.]

**Notice:** [This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.]

**Release:** [The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.]

## Coexistence of UWB-BANs with other Wireless Systems

NICT, Japan

### Motivation

## UWB as a potential candidate for on-body communications:

- Low implementation complexity (critical for low power consumption)
- Low transmitting power (safety and low interference)
- It might allow bit rate scalability from LDR to HDR

It is important to address the interference caused by/to UWB devices in order to guarantee not conflicting coexistence with other licensed or unlicensed wireless systems.

### **Motivation**

Some results on the coexistence between UWB systems and existing wireless systems can be found in the literature and regulatory forums.

• Caveat: assumptions might give misleading conclusions, like UWB devices are assumed uncontrolled radiators transmitting 100% of the time at maximum power.

Victim terminals: FWA or WLL, PP, UMTS, WiMax.

### Scenario

## UWB devices are located indoor forming a hot spot

 those are placed at random on-body and from coordinator (on-body) to gateway.

### Interference is evaluated taking into account:

• architecture (signal model), possible power control, traffic characteristics (activity factor) and superposition of UWB signals.


An adopt criterion of coexistence (acceptable level of interference) is that victim operators accept r dB degradation in receiver sensitivity:

$$\left. \frac{C}{N} \right|_{\mathbf{dB}} - \left. \frac{C}{N+I} \right|_{\mathbf{dB}} = r \, \mathbf{dB}$$

$$\frac{N+I}{N} = 10^{r/10}$$

- $r = 1 \, \mathrm{dB}$  is chosen as reference and according to ITU Recommendation F.758-2 (long-term interference to fixed services), when considering interference from secondary services and unwanted emissions.
- This is equivalent to I/N = -6 dB.

$$r = 1 \, \mathrm{dB}$$
 or  $I/N = -6 \, \mathrm{dB}$ 



The victim terminal's thermal noise is given by

$$N = -174 \text{ dBm/Hz} + 10 \log_{10}(BW_v) \text{ Hz} + N_f + L_o (2 \text{ dB})$$

Thus, the maximum allowed interference is given by

$$I_{\text{max}} = N + 10 \log_{10} (10^{r/10} - 1)$$

•  $I_{\text{max}}$  is the point of departure to ensure conflict-free coexistence.

System	Parameters $(r = 1 \text{ dB})$	$f_l$ (GHz)	$f_h$ (GHz)	$I_{\max}$ (dBm)
FWA []	$N_f = 5  \mathrm{dB}$	3.475	3.525	-95.88
	$BW_v = 50\mathrm{MHz}$			
	$N_f = 5  \mathrm{dB}$			-101.4
	$BW_v = 14\mathrm{MHz}$			
PP []	$N_f = 6  \mathrm{dB}$	4.4	5.0	-95.87
	$BW_v = 50\mathrm{MHz}$			
UMTS []	$N_f = 9  \mathrm{dB}$	2.165	2.170	-101.88
	$BW_v = 50\mathrm{MHz}$			
WiMax []	$N_f = 4.6\mathrm{dB}$	3.4	3.8	-107.42
	$BW_v = 3.5\mathrm{MHz}$			
	$N_f=4.6\mathrm{dB}$			-103.27
	$BW_v = 10 \mathrm{MHz}$			

#### Scenario

- UWB devices are located indoor and on-body plus from coordinator (on-body) to gateway, communicating with TDD (uplink).
- UWB antennas with 0 dBi gain.
- Victim terminals are either inside or outside the hot spot.

## Signal model

- UWB signal model corresponds to any UWB candidate.
- For the sake of illustration TH-UWB is considered.

#### **TH-UWB**

$$x(t) = \sum_{k} b_{k} p_{k}(t - kT)$$

$$p_{k}(t) = \sum_{n=0}^{N_{f}-1} w(t - nT_{f} - c_{k,n}T_{c})$$

- The pulse waveform w(t) is either baseband or passband. So, x(t) is carrier or carrierless.
- The transmitting power of x(t) has to satisfy a regulatory spectral mask. It might change depending on the frequency band, but as worst case scenario a PSD of -41.3 dBm/MHz is considered.

$$Pt = 10 \log_{10} \left( \int_0^\infty |X(f)|^2 df \cdot 10^{-41.3/10} \right)$$
 (1)

- Transmitting antenna and radio-front-end are assumed to introduce negligible distortion.
- Interference capture by a victim terminal is given by

$$Pr_v = 10 \log_{10} \left( \int_{BW_v} |X(f)|^2 df \cdot 10^{-41.3/10} \right)$$

• The aggregate interference on a victim terminal

$$I_{\text{UWB}} = \sum_{m} Pr_v^m \, \chi_m \, Gr_v \, L(d_m)$$

•  $\chi_m$  is the activity factor of the *m*th UWB device. So, traffic can be modeled by different bit rates and activity factors.

## **Path loss**

The propagation can be either indoor or outdoor, but for the sake of simplicity indoor (BAN) path loss is assumed

$$L(d) = P_0 + n \log_{10}(d/d_0)$$

•  $P_0 = 50.5 \, dB$ ,  $n = 7.2 \, and \, d_0 = 0.1$ .

### **MCL**

A conventional way to deal with coexistence is to compute zones around UWB hot spots, where victim receivers would not exceed a certain level of interference.

- Thus, computing the minimum distance required between a UWB device and a victim receiver to ensure the maximum allowed interference  $I_{\text{max}}$  is not exceed (MCL).
- Minimum Coupling Loss:

$$MCL = P_t + G_t - L_o + Gr_v - I_{\text{max}}$$

$$\widehat{d} = \arg\min_{d} L(d) \ge MCL$$

### **MCL**

#### Example

- As example, x(t) employs a Gaussian pulse and a carrier signal spanning  $2\,\mathrm{GHz}$  bandwidth around 4–9 GHz.
- From Equation 1 computed numerically,  $P_t = -10.6 \text{ dBm}$ .
- For simplicity  $Gr_v = 0$  dBi, and  $I_{\text{max}}$  values are taken from the previous Table.

# **Preliminary Results**

system	$I_{\max}$ (dBm)	MCL (dBm)	L(d) (dBm)	$d\left(\mathbf{m}\right)$
FWA (50 MHz)	-95.88	83.28	87.85	0.3
FWA (14 MHz)	-101.4	88.8	92.67	0.35
WiMax (3.5 MHz)	-107.82	95.22	99.11	0.43
WiMax (10 MHz)	-103.27	90.67	94.41	0.31

## Still a work in progress

To be done: propagation outdoors, power control, computing  $I_{\text{UWB}}$ , impact of interference from other services to UWB-BAN systems, etc.