#### **Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)**

Submission Title: [Additional Considerations for Maximizing the benefits of an OFDM PHY for SUN]

Date Submitted: [7 May, 2009] Source: [Shusaku Shimada] Company [Yokogawa Co.] Address [2-9-32 Nakacho-town Musashino-city Tokyo, 180-8750 Japan] Voice:[+81-422-52-5543], FAX: [+81-422-55-7311], E-Mail:[shusaku@ieee.org] Re: []

**Abstract:** [To encourage the constructive discussions and their fruitful merger of OFDM PHY proposals, then to consolidate a few PHY technologies including NB-FH PHY, some considerations regarding OFDM PHY are submitted.]

**Purpose:** [Contribute to the 15.4g SUN standardization process.]

**Notice:** This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

**Release:** The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

## Additional Considerations for Maximizing the Benefits of an OFDM PHY for SUN

Considerations is primarily based on "Affordable OFDM for SUN" proposal (15-09-0289-00-004g) by Steve Shearer, but also relating to all OFDM PHY proposals and other PHY proposals including NB-FH PHY as well.

### Shusaku Shimada


### Back Ground

- Needs of relaxing the selectivity requirements like as 15.4-2006.
  - Wider channel spacing relative to the signal bandwidth.
  - 0dB adjacent channel rejection and 30dB alternate channel rejection in term of RX.
  - -20dBm max. interferer have to be handled.
- Be accommodated in several international regulatory domains.
  - Channel spacing: 150kHz, 200kHz, 600kHz, 2MHz, or more.
- Perspective of message timeliness and extreme low power.
  - Generator utilities (Solar Panel, Wind Gen., Plugged in/out HEV.) have to communicate timely.
  - Timely alert messaging by energy harvesting or scavenging, e.g. fuel/liquid flow meter.
  - Collective "Commissioning" for deployment / maintenance.
- Enhance reliability and cell radius of tower top BS.
  - Provisioning of Multi-antenna system
- Needs of diverse deployment scenarios by multi-radio node.
  - Multiple radio device belongs to multiple mesh networks (UCG) for diverse service in the future.
  - Segregating a few service networks each other or to enhance traffic engineering.

## Flexibility for Global Channel Plan by OFDM (1)

- Maintain sub-carrier spacing of 18.75kHz and allow,
  - Full 14 sub-carriers 300kHz signal for 400 or 600kHz channel-spacing with stringent ACPR in Japan.
  - 8 sub-carrier for 168.75kHz signal for 200kHz (world wide active RFID band) channel spacing.
  - 6 sub-carrier for 131.25kHz signal for 150kHz channel spacing for a few regulatory domains.
  - Consequently, SFD need to be either Length-11 Barker or Length-5 Barker with null sub-carriers.
- Flexible sub-carrier usage for each channel plan to facilitate,
  - Adjacent channel rejection performance of TRX.
  - Alternate (next to adjacent) channel rejection performance of TRX.
  - Alleviate RX blockage due to strong interferer.
- Simple windowing at both TX and RX alleviate,
  - SOP performance degradation, since the sub-carriers at band edge are nulled out as guard band.
  - Co-channel interference impediment due to asynchronous specular reflection.

## Flexibility for Global Channel Plan by OFDM (2)



## Flexibility for Global Channel Plan by OFDM (3)

<IEEE 802.15-07-0621-03-wng0>

[ Chinese 779-787MHz Band ]

SRD only usage

- Frequency : 779MHz 787MHz ( License Exempt Band )
- Bandwidth : No restriction
- Modulation : Digital Modulation
- No other requirement known : no LDC ( Low Duty Cycle ), no LBT ( Listen Before Talk )
- Transmit Power : 10mWe.i.r.p.

#### [Korean 908.5-914MHz Band]

#### Shared by RFID & SRD

- Frequency : 908.5 914MHz < 200kHz channelization >
- Modulation : FHSS or Narrow Band Modulation
- Other requirement known : FHSS only, FHSS + LBT ( Listen Before Talk ), LBT only
- Transmit Power : Maximum Power 1W with 6dBi max. Antenna Gain

## Extreme Low Power by 16 point OFDM (1)

### • Ensuring extreme low power by,

- low complexity of 16 point iFFT/FFT.
- OFDM inherent parallelism, e.g. multi-carrier parallel processing system.
- relatively low symbol rate and subsequent reduced clock frequency of signal processing.
- Alleviated analog linearity requirements by,
  - relaxed PAPR of 12 or less sub-carriers and possible peak cancellation by extra sub-carrier.
  - MCS without higher order linear modulation like 64 QAM.


### • Full function node with relay capability also enjoys,

- 16 point OFDM to combine with "Coordinated Sample Listening" and resulting low power.
- prepended of repetitive OFDM headers to work as "Wake up frame".
- reduced function node to hear reliably and detect smartly the wake up frame. e.g. robust MCS.
- supporting on going IEEE802.15.4 TG-e MAC amendment activities.

## Extreme Low Power by 16 point OFDM (2)


#### Coordinated Sample Listening and Local Scheduling By Wei Hong, et al. <br/> Vei Hong, et al.

- Include channel sampling phase and period in ACK payload
- Sender wait to transmit right before receiver's next channel sampling time



## Introduce 64 points sequenced OFDM (1)

- Optional 64 point sequenced OFDM to allow,
  - 4 basic 16 pts OFDM signals to be used in time-alternate manner for enhanced timeliness.
  - in other words, slow frequency hopping to increase reliability without time synchronization.
  - Orthogonal freq. Sequences (4 basic 16 pts OFDM: 1,2,3,4) : e.g. 2-4-1-3, 3-1-4-2, 1-3-2-4, 4-2-3-1
  - Preamble only prepend at first signal, and SFD for all 4 sequenced signals.
- Co-channel interference avoidance to alleviate,
  - Mesh capacity degradation by interference between multi-hop links.
  - Network-wide synchronization requirement especially for urban dense deployment scenario.
- Improve timeliness and reliability by,
  - reducing multi-hop latency and retry transaction latency.
  - "Retry in advance" using series of 16 pts OFDM signals by enhancing time & frequency diversity.
  - decoding two or more orthogonal puncturing patterns in combined reduced rate, e.g.  $2/3 \ge 1/3$



## Provisioning of Multiple Antenna Node for future

- Tower-top base station in case of tree topology.
  - OFDM alleviates the complexity of possible MRC.
  - OFDM facilitates possible transmitter side antenna selection using the channel reciprocity.

#### • Leaf node with multiple antenna.

- 16 points OFDM alleviates the channel estimation of each antenna chain by sharing DSP functions.
- Resulting receiver side antenna selection using SFD.
- Select identical antenna as resulting receive side antenna selection.
- STBC
  - If any antenna selection or RX-MRC is not possible, of course STBC may be feasible.

### Provisioning of Multi-radio Node for future

- Diverse deployment scenarios by multi-radio node.
  - OFDM system could append the additional communication capacity on existing NB-FH systems.
  - Multi-radio handheld tool for collective commissioning and maintenance, e.g. Electricity, Gas, Water.
  - Multi-radio device would share parallel processing resource by each radio systems, e.g. Viterbi.

- Traffic eng. to adapt with the node population and its trend.
  - Multi-radio gateway node to backhaul : OFDM on OFDM, OFDM on NBFH.
  - restructuring UCG (Unified Channel Graph) to merge or separate by multi-radio node, e.g. OFDM.
  - Relatively easy overlay deployment using plurality of available frequency channels.

# Thank you

[Reference]

15-07-0621-03-wng0-Commonality-Enhancement-for-Sub-GHz-WPAN 15-07-0712-00-wng0-Supplement-Commonality-Enhancement-for-Sub-GHz-WPAN 15-08-0109-02-004d-WW-BPSK-with-AFA-provisioning 15-09-0262-00-004g-ofdm-option 15-09-0289-00-004g-affordable-ofdm-for-the-sun-phy 15-09-0294-00-004g-affordable-ofdm-for-sun-detailed-proposal