Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: Multi-Rate PHY Proposal for Europe - Presentation

Date Submitted: July 2009

Source: Michael Schmidt, Atmel **Contact:** Michael Schmidt, Atmel

Voice: +49 351 6523-436, E-Mail: michael.schmidt@atmel.com

Re: TG4g Call for proposals

Abstract: PHY enhancements towards TG4g supporting multiple data rates

Purpose: PHY proposal for the TG4g PHY amendment

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Overview

This document guides through the proposal

PPDU

| Octets: 8 | 1 | | 2 | 4 2047 | | |
|-----------|-----|--------------------|------------------------|-------------------|-------------------|---------------------|
| Preamble | SFD | Data rate 2 bit | Frame length 11 bit | Reserved 2 bit | (Parity) 1 bit | PSDU (incl. FCS-32) |
| SHR | | PHR | | | | PHY payload |

SHR and PHR: fixed rate of 25 kbit/s

PSDU: variable rates out of {25,50,100,200} kbit/s

Data Rate Modes

- Fixed chip rate of 200 kchip/s
- GMSK
- Different data rates are obtained by appropriate coding.


| DataRateMode | Coding | PSDU Data rate [kbit/s] | Remark |
|--------------|----------------|----------------------------|-------------------------------------|
| 1 | C(32,4) | 25 | Mandatory Coherent, non-coherent |
| 2 | C(16,4) | 50 | Mandatory Coherent, non-coherent |
| 3 | C(8,4) | 100 | Optional, coherent |
| 4 | C(4,4) uncoded | 200 | Optional, coherent, (non-coherent) |

Key Benefit

 Moderate RF bandwidth of 200 kHz with regard to the lowest data rate of 25 kbit/s

- This considerably simplifies low-IF and zero-IF transceiver design w. r. t. an equivalent 25 kHz RF bandwidth of a narrow band approach.
- Robustness against clock offset is +/- 20 ppm (+/- 40 ppm overall)

Laurent Approximation for GMSK



C(32,4) Coding

- Always used for SHR and PHR (assures reception under worst conditions).
- PSDU encoding for DataRateMode 1, leading to a data rate of 25 kbit/s.
- ML soft-decision decoding
- Code construction:
 - Balanced code with d min = 14
 - Cyclic shift of a 1-extended {m=5}-sequence implying good auto-correlation properties
 - Reasonable spectral properties
- Optimal linear C(32,4) code: d_min = 16
- Coherent and non-coherent demodulation

C(16,4) Coding

- PSDU encoding for DataRateMode 2, leading to a data rate of 50 kbit/s.
- ML soft-decision decoding
- Code construction:
 - Balanced code with d min = 6
 - Reasonable spectral properties
- Optimal linear C(32,4) code: d_min = 8
- Coherent and non-coherent demodulation

C(8,4) Coding

- PSDU encoding for DataRateMode 3, leading to a data rate of 100 kbit/s.
- GMSK pre-coding
- ML soft-decision decoding
- Code construction:
 - BCH (7,4) code extended by 1
 - Non-balanced code with d_min = 4
 - GMSK-like spectral properties due to pre-coding
- Optimal linear C(8,4) code: d_min = 4
- Coherent demodulation only

No Coding

- PSDU encoding for DataRateMode 4, leading to a data rate of 200 kbit/s.
- Flexible choice for additional outer coding
- Coherent demodulation recommended

Targeting Lower Data Rates?

- C(32,1)
 - Maximum receiver gain is only 3dB relative to C(32,4)
 - Influences SHR
- C(128,1)
 - Interesting option for EU band, since the output power is restricted to -4.5 dBm/ 100 kHz for some channels
 - Very low data rate of 1.562 kbit/s
 - Differential pre-coding at the chip and at the bit level
 - Requires a dedicated SHR.

Coherent Demodulation

- Phase Tracking based on decoded symbols
- Residual phase error

$$\delta\phi = N_R \cdot 2\pi \cdot \frac{f_c}{f_{chip}} \cdot \delta p$$


GMSK

- Modulation index $h = \frac{1}{2}$ allows simple coherent detection, based on Laurent approximation.
- Unlike BPSK, problems related to I/Q images are relaxed.
- The influence of BT in {0.3,0.5} is relatively low for coded transmission (coherent and non-coherent).
- For uncoded GMSK, coherent demodulation is recommended
 - better performance
 - simpler to equalize


Simulation Model

- Low-IF receiver with 200 kHz IF
- 4-th order Butterworth filter of 200 kHz BW centered at IF (moderate pole-Q)
- I/Q limiter with 8 MHz oversampling + discrete-time post filtering
- LNA noise: -174 dBm/Hz + 5 dB noise figure
- I/Q mismatch: -45 dB image
- DC suppression: 50 kHz
- Clock offset tolerance: +/- 20 ppm
- Synchronisation: initial timing offset and clock offset
- Coherent detection: first-order phase decision feedback control loop
- Non-coherent detection: chip differential
- Equalization: none


Coherent, 20 octets



Non-coherent, 20 octets



2047 octets, 40 ppm clock offset



Channel Assignment

- 12 channels within 863-870 MHz (band G)
- Avoid RFID interrogators
- Avoid alarm channels
- Use sub-bands G1 and G2

| channel number | 1 | 2 | 3 | 4 | 5 | 6 |
|----------------------|-------|---------------|-------|-------|-------|--------|
| $f_c [\mathrm{MHz}]$ | 863.4 | 863.8 | 864.2 | 864.6 | 865 | 865.4 |
| channel number | 7 | 8 | 9 | 10 | 11 | 12 |
| $f_c [\mathrm{MHz}]$ | 866 | 9 <i>00</i> 0 | 967.9 | 967.9 | 969 9 | 868.95 |

Outer FEC

Additional more complex outer forward error-correcting coding is useful, especially for the high rate mode when considering large PSDU lengths. The sensitivity gap to the low rate encoded header can be exploited.

- Algebraic codes (e.g. BCH codes)
 - Pragmatic approach, since it can be shifted to the upper layers.
 - However, soft decision gain is lost. Bounded Minimum Distance Decoding is not simple.
 So, why shifting it to other layers?

Outer FEC

- Convolutional codes
 - Since decoding usually applies soft decisions, the recursive encoder of the GMSK modulator should be taken into consideration. Interleaving may be useful too.
- LDPC codes
 - State of the art
 - Iterative decoding might be affordable due to the low data rate.

Extension to 902-928 MHz

- This PHY is mostly applicable if FH is desired anyway.
- Channel spacing could be changed to 400 kHz.
- BT = 0.5 only

Extension to 870-873 MHz

- There are rumors on the availability of this frequency band.
- This PHY might be directly applicable.

Possible Extension to 902-928 / 2400-2483.5 MHz

Targeting *digital modulation*_according to FCC part 15.247 (This allows high transmit power without FH.)

Chip rate [kchip/s]: 1000 kchip/s

Modulation: GMSK

Coding: C(128,1), C(64,4), C(16,4), C(8,4)

PSDU data rates in [kbit/s]: 7.8125, 62.5, 250, 500

Channel spacing: 2000 kHz