15 July 2009

doc.: IEEE 802.15-<09-0546-00-0007>

#### **Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)**

Submission Title: [Change in Japan's Energy Saving Law, 2009]

Date Submitted: [15 July 2009]

**Source:** [(1)Tom Matsumura, VLCC]

Address [(1)2-15-9 Nishi-Gotanda Shinagawa-ku Tokyo 141-0031 Japan]

Voice:[(1)81-3-5437-5120]

E-Mail:[(1) tom@naka-lab.jp]

**Re:** []

**Abstract:** [The Change in Japan's Energy Saving Law in April, 2009]

**Purpose:** [Contribution to IEEE 802.15 TG7]

**Notice:** This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

**Release:** The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.



# The Change in Japan's Energy Saving Law in April, 2009.


Tom Matsumura,
Executive Director
Visible Light Communications
Consortium



## **Objective:**

1. Focus on the energy saving in the office/household section, which has been increasing at 1.4 times between 1990 and 2005 (the largest increase in energy consumption).

2. Strengthen the energy saving especially in the office/household section (offices/convenient stores as well as houses/buildings).



## Action Plan 1


#### <Offices/Factories>

- One energy unit was a company unit including factories only before. From April, the company unit includes not only factories, but also offices (including head office and sales offices, etc). The unit using an energy more than 1,500 KL annually needs to be reported to Japanese government.

#### <Franchise chains/Convenient stores>

- Franchise chains were not counted before as one energy unit. From April, a franchise-chains such as convenient stores is counted as one energy unit. The unit using an energy more than 1,500 KL annually needs to be reported to Japanese government.





### **Action Plan 2**

- In order to construct a large house/building (more than 2,000 m²), the owner needs to report its energy saving plan to Japanese government.
- The sales agent of houses/buildings need to introduce the efficient energy saving methods.
- The energy saving methods need to be explicitly indicated.

Grasp of the energy consumption in the whole company (1 year from April 2009)



Energy consumption more than 1,500kl ?



Notification to Bureau of Economy (FY 2010)



Designation for Specific enterprise or Franchise chain enterprise



Penalty of less than 500,000 yen when no notification or false notification.

No need to notify to Bureau of Economy

The aim of the enterprise whose annual energy consumption becomes more than 1,500kl

**Retail store**: more than about 30,000 m<sup>2</sup> **Office**: more than 6 million kWh / 1year **Hotel**: more than 300 – 400 at number of

guest rooms

**Hospital**: more than 500 – 600 at number of beds

**Convenience store:** more than 30 or 40 stores

Fast food shop: more than 25 shops Family restaurant: more than 15 brunches

Fitness club: more than 8 studios

#### [Caution]

The consumption of the energy is different by the geographical condition (the location) of the business establishment or the constitution (for example, city hotel and budget hotel in case of hotel, or general hospital and medical treatment type hospital in case of hospital) of the institution. It shows as a general standard.

