doc.: IEEE 802.15-15-09-0648-00-0007

#### **Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)**

**Submission Title:** [Samsung VLC MAC proposal]

**Date Submitted:** [22 September, 2009]

Source: [Sridhar Rajagopal, Doyoung Kim, Ying Li, Taehan Bae, Jaeseung Son, Eun Tae Won, Farooq

Khan] Company [Samsung Electronics]

Address [1301 E. Lookout Drive, Richardson, TX 75082, USA]

Voice:[1-972-761-7748], FAX: [1-972-761-7909], E-Mail:[ srajagop@sta.samsung.com]

**Re:** []

**Abstract:** [Initial proposal for VLC MAC for IEEE 802.15.7 standardization]

**Purpose:** [Contribution to IEEE 802.15.7 VLC TG]


**Notice:** This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

**Release:** The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

### Outline

Applications
Frame structure
Frame types
Access mechanisms
MAC header
Visibility support
Channel selection and association
Multiple color channel support
Mobility support for handoff
Other MAC features


### Applications considered for VLC MAC




### VLC device classification

	Infrastructure Mobile		Vehicle-mounted	
Fixed access point	Yes	No	No	
Power supply	Ample	Limited	Moderate	
Form factor	Form factor Unconstrained		Unconstrained	
Light source	Intense	Weak	Intense	
Physical Mobility	No	Yes	Yes	
Range	Short/long	Short	Long	
Data rates	High/Low	High	Low	

# Unique requirements for VLC (Infrastructure support)




## Unique requirements for VLC (Point-and-shoot for mobile)




Reference: W.C. Kim et al., "Efficient resource allocation scheme for visible-light communication", Proc. Of SPIE, Vol. 7234. pp. 72340M-72340M-9, 2009.

## Single MAC design


#### **MAC** application modes




### **VLC** Topologies




## Common VLC frame structure (Virtual slots)



### VLC frame slot configuration



## Access mechanism (TDD - full duplex for visibility with spatial separation)




## Frame format types

Frame format type	Application	Slots used	Use
Beacon frame	VLAN, IB, VB	Beacon slots	Used by infrastructure to indicate start of frame and define number of slots to be allocated for contention, uplink and downlink. It also can tell location of active and/or in-use slots and which slots are free. Beacon frames are broadcast, have no security and do not require any acknowledgement.
Management frame	VLAN, P2P	Uplink, downlink, data slots	Are used to establish network. Are used for association, hibernation, channel change, identification, security, PHY/MAC capabilities, logical mobility/handoff etc.
Acknowledgeme nt frame	VLAN, P2P	Uplink, downlink, data slots	Are used to acknowledge receipt of transmission (or lack of). Transmits the received sequence number of frames. Acknowledgements can be of multiple types such as single, packed or burst type
Data frame	VLAN, P2P, VB, IB	Uplink, downlink, data slots	Used for transmitting data in all modes. Can be of different types such as single, packed or burst type
Visibility frame	VLAN, P2P, VB, IB	Infrastructure: Contention, uplink slots, unused downlink slots for continuous visibility Mobile device: unused slots for point-and — shoot	Used by infrastructure to maintain visibility at ALL times in between frames and during RX and idle modes. Can be used by mobile nodes for point-and-shoot. Sends a known visibility pattern of a certain visibility percentage. Can also be used for dimming support with visibility pattern adapted to the dimming requirements (with the data being adapted to dimming pattern as well)

#### doc.: IEEE 802.15-15-09-0648-00-0007

MAC header fields	Explanation on use	Beacon	Management	Acknowledgement	Data	Visibility
Version number	Allows to distinguish future versions of the standard		Set to default for current standard version			
Secure	Mentions whether frame is secure	No security		Frame dependent		No security
ACK policy	Mentions the acknowledgement policy used	No ack		Frame dependent		No ack
Frame type	Mentions the type of frame such as beacon, management, data	Beacon	Management	Acknowledgement	Data	Visibility
Frame sub- type (dependant on Frame type)	These fields are set to be dependent on the frame type	IB, VB, VLAN	Association, hibernation, channel change, device ID, PHY/MAC capabilities, security, mobility	ACK, No ACK, Negative ACK, Burst ACK, Burst Negative ACK	Single, packed, burst	Percentage visibility (or dimming)
Retry	Mentions if any retry is needed	No retry	o retry Frame dependent			No retry
Src address	Source address of TX			Frame dependent		
Destination address	Receiver address – to identify intended recipient or recipients in case of multicast or broadcast	Broadcast	Frame dependent			
Sequence number	Tells sequence number of current PDU	No sequence number	*			No sequence number
Num PDUs per frame	Tells how many PDUs can be expected in this frame	single 1 for single, 'n' for packed, burst			No PDUs	
Reserved fields	Allows for future expansions of the MAC header	Not used for current standard				

### VLC MAC Data types



## Modes used by different applications

Application	Type of communication	Data and control mode
P2P, VLAN	Management, Acknowledgement	Single
IB, VB, VLAN	Beacon	Single
P2P	Data	Burst, Packed
VLAN	Data	Single, Packed
IB	Data	Single, Packed
VB	Data	Single

## Visibility

### **Necessity**

- Alignment (Device discovery, negotiation, connection)
- Visible guiding for user alignment
- Infrastructure continuous light output
- Blinking for unexpected interference, disconnection warnings

### Visibility on PAR


- Scope of proposed Standard: This standard .... The visible light spectrum extends from 380 to 780 nm in wavelength. The standard is capable of delivering data rate sufficient to support audio and video multimedia services and also considers mobility of the visible link; ...; and a MAC layer that accommodates visible links. ....
- Ref: 15-08-0656-01-0vlc-par-document.pdf

## Support for basic visibility patterns

Visibility pattern (Percentage visibility)


```
11111 11111 (100%)
             (90\%)
11110 11111
11110 11110
11101 11100
11001 11100
10001 11100
00001 11100
00001 11000
00001 10000
             (10%)
00001 00000
00000 00000
              (0\%)
```

### Support for higher resolution visibility



## Generating higher resolution visibility patterns

Fixed low resolution visibility patterns



### Example algorithm

It is preferable to have patterns that are chosen closer to the desired visibility to maximize transitions

For example, for attaining 25.3% visibility, we would like to maximize the use of 20% and 30% visibility patterns.

This can be done by using 20% pattern 47 times and 30% pattern 53 times

Number of ones = 2\*47 + 3\*53 = 253

Total number = 10\*47 + 10\*53 = 1000


Attained visibility = 25.3%

## Extended preamble mode for visibility

ldle	Preamble	Control	Data	ldle	Preamble	Control	Data
(a) Default transmission							
Preamble	Preamble	Control	Data	Preamble	Preamble	Control	Data

(b) Transmit extended preamble for visibility and for faster and better synchronization

## Example of extended preamble mode




## Link adaptation for dimming support

**Dimming cycle patterns of infrastructure should be notified to VLC RX device**, so that the VLC device could adapt to the dimming pattern


Infrastructure VLC may receive a dimming request from a dimmer triggered by user

Propose to use *a link adaptation timer* that delays the time between the dimming request and the actual dimming of the light source.

With this knowledge of an incoming dimming, the link between the devices can be adapted to work at a new (lower) data rate (if dimmed) without requiring the link to be interrupted or possible link failure.



### Multiple channel support



## Exchanging capabilities and channel selection during device discovery process

Device 2 (host/master) Transmit on M1 channels Send channel colors supported, guard channels, application requirements Exchange capabilities Transmit on K channels Send channel colors supported, guard channels, application requirements Send RX COI report for K channels Send TX CQI report for K channels Channel selection Inform channel(s) used for TX and RX and access (TDD/FDD) Data transfer on agreed channel(s)

Device 1 – M1 colors

Device 2 - M2 colors

 $K = M1 \cap M2 - common colors$ 

CQI – Color Quality Indicator report

## Capabilities Information Element for device discovery

### PHY capabilities:

- Colors supported
- Data rates
- Guard colors for each supported color


### MAC capabilities:

- Uni-directional traffic support
- Bi-directional traffic support
- P2P support
- P2MP support
- Visibility/Dimming support

### Multiple channel resource assignment

MS (Destination) reports available channel resource

#### Can expand to many channels




Ch	Bit	R	G	В
1	000	0	0	0
2	001	0	0	×
3	010	0	×	0
4	011	×	0	0
5	100	0	×	×
6	101	×	0	×
7	110	×	×	0
8	111	×	×	×

### Channel hopping for interference avoidance

In order to avoid interference by hopping pattern

#### Resource enhancement



pattern set	001	011	101
Frame/time slot	HP 1	HP 2	HP 3
1	R	G	В
2	В	G/R	В
3	G	R/B	G
4	G/R	В	G/R
5	G/B	R	G/B
6	R/B	G	R/B
7	G	В	R
8	В	R	G
9	R	G/B	R

### Multiple channel hopping

Hopping based some frame/time slot

Hopping and non hopping mode support

Multi or single channel support per each MS channel

### Blinking notification

Depending on the FOV, TX power and the mobility of devices, it is possible that the link may occur only in 1 direction.


In such cases, the mobile needs to change the visibility indication from continuous visibility for pointand-shoot to blinking indication


For example, if the infrastructure cannot receive uplink but the mobile is able to receive downlink, the AP can indicate to mobile about the lack of reception and request a visibility indicator change for the user


The mobile can then change from point-and-shoot mode to blinking mode to indicate the user that the connection may be getting disconnected.


This indication can be applied to both P2MP and P2P modes of operation


## Supporting mobility across piconets

















### Mobility support within a piconet

#### Fractional cell assignment based on signal detection

- enhancement capacity and avoiding interference
- low power consumption







Additional fields in management payload	Explanation on use		
Src_multi_info	Source multiple channel resource assignment		
Des_multi_info	Destination multiple channel resource assignment		
S_info	Time slot information for multiple channel		
H_pattern	Multiple channel hopping		
VF_info	Visibility frame notification for source and destination		
Src_mode	Granular and single source notification		
G_cell_ID	Granular cell assignment		
Fractional_Src	Fractional source notification		
Mode_type	Milticast/broadcast/unicast announcement		
S_Release_slot	Start and release slot for broadcasting		
Spatial mobility	Request spatial mobility to AP		

## Other MAC features under development that is required for IEEE 802.15.7

Security

Power saving schemes

Others

### Conclusion

	IEEE 802.15.7 VLC			
Application	VLAN/IB/VB	VLAN P2P		
Link	Downlink	Uplink	Downlink/Uplink	
wavelength		380nm~	780nm	
Optical channel	Multiple	Multiple (possible) Single (preferred)		
Line coding	8B10B			
Duplexing	TDD Half (except for visibility)			
Frame slot	Slot		Non slot	
Data rate	6.4 Mbps (Min) / 96 Mbps (Max)			
Mobility	Support		None	
Frame type	Data/Visibility/Management/Beacon/Ack		Data/Visibility/Management/Ack	

### Summary

An initial proposal for VLC MAC is presented for TG7 consideration

Supports P2P, IB, VB, VLAN applications

Single MAC design with single MAC header to support multiple applications

Provides support for visibility/dimming and mobility features


doc.: IEEE 802.15-15-09-0648-00-0007

## Appendix

## **Spatial Mobility**

### MS (Destination) request spatial mobility to APs

- Support VLC device mobility
- Low power consumption




### Slots assigned by mobile movement

### Granular cell assignment

- support VLC device mobility
- optical source grouping






Granular cell ID n

### Fixed slots assignment with re-use

### Granular cell assignment

- support VLC device of IB service mobility
- optical source grouping

Hard hand of



Time slot reuse for interference avoidance