Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: [ZES UWB Band Plan Proposal]
Date Submitted: [10 March, 2010]
Source: [Tim Harrington] Company [Zebra Enterprise Solutions]
Address [2940 N. 1st Street, San Jose, CA. 95134. USA]
Voice:[+1 408 473 8513], FAX: [+1 408 473 8501], E-Mail:[tharrington@zebra.com]

Re: [Band Plan Proposal for UWB RFID PHY.]

Abstract: [This document proposes a simple band plan that allows a single tag to be used throughout North America, the EU, and China, with an alternate band for Korea and other countries that require frequencies above 7 GHz.]

Purpose: [To resolve outstanding issues on the current baseline proposal]

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Submission

UWB PHY Band Proposal

Tim Harrington

tharrington@zebra.com

+1-408-473-8513

Background

 This presentation is provided to foster further discussions introduced in documents 802.15-10-0147-00-004f and 802.15-10-0148-00-004f

Goals

- Primary
 - Compliance with regional radio law
 - Maximize value of new, and changes to, regional radio law
 - Provide cost effective approach to promote accelerated growth to UWB in RFID/RTLS industry
 - Co-exist with current standards
- Additional Goals
 - Allow 802.15.4a interoperability with minimal performance trade-offs
 - Provide path to lowest cost tag

Consistency with Regional Radio Law

- Compliance Only Possible in Regions that have Defined Laws
- "Early Adopter" Countries Serve As Models For Countries Which Do Not Yet Have Rules
 - ETSI and FCC standards serve as guides to many countries regulatory agencies
- Standards Influence Changes in Local Radio Law
 - Japan adopted 2.400-2.483 GHz after IEEE 802.11 was published
 - Move from 2.470-2.497 GHz
 - South Korea adopted "Wide Band" DSSS rules allowing 80 MHz DSSS after publication of ISO 24730-2
 - Expansion from maximum bandwidth of 26 MHz


Maximize Value of Changes in Radio Law

- New Rules Provide the Ability to Find "Sweet Spots" of Commonality
- During Development of 4a
 - EU rules were not yet set
 - Chinese Rules were not yet set
 - Canadian rules were not yet set
- The Establishment Of These Rules Afford An Opportunity That Was Not Available To Members Of The 4a Committee

Accelerate Growth of UWB in RFID/RTLS Industry

- Key Premises
 - Standardization is conducive to market growth
 - RFID Standards that allow passage across international boundaries have widest applicability and desirability
 - Key 4f goal is to foster international adoption of RFID devices for rapid market growth
 - Low cost tags are a vital component to rapid market growth
- Cost Components
 - High volume, single product manufacturing is key to low cost
 - Multiple bands requires multiple products or higher cost multiple frequency transmitters
 - Lowest cost tags are single frequency devices
- Key Assertions
 - Single frequency tags are not conducive to remote frequency changes
 - PHY standards with multiple bands have less value than single band standards
 - 1 Band would be optimal, but is not attainable at this time
 - ...But 2 is better than 3 and provides a potential path to 1
 - International adoption of a single frequency will be hampered by more bands
 - Single frequency, high volume product is less costly than a filter

Commonality Possible with 2 Bands



- ~ 37.5% of World Population has UWB Regulations Defined
- ~ 35% of World Population can be accommodated by 1 Band
- 93 % of Currently Available Market by Population Can Use 1 Band

Band Plan Recommendation

- Band 0 6.55 GHz CF, 570 MHz -10 dB Bandwidth
 - Allows single tag that provides maximum compliance compatibility – NA, EU, China
 - Filtering can be achieved at very low cost
 - Filtering assures minimum interference to 802.15.4a UWB systems
 - > 500 MHz Band width assures compatibility with efforts to redefine UWB in EU as minimum of 500 MHz
- Band 1 7.75 GHz CF, 570 MHz -10 dB Bandwidth
 - Lowest common frequency for maximum range
 - Would no Require DAA in the EU
 - Allows single tag that can be compatible throughout Asia and the EU
 - + Items 2-4 from above