

Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: [SFD discussions for LECIM FSK-PHY]

Date Submitted: [Jan. 2012]

Source: Mi-Kyung Oh, Sangsung Choi, Kwang-Roh Park (ETRI)

Voice: +82 42 860 5680, FAX: +82 42 860 5218, E-Mail: ohmik@etri.re.kr

Re: [802.15.TG4k]

Abstract: This contribution is prepared to discuss about SFD sequence for FSK PHY.


Purpose:

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

FSK Packet Format

- PHY packet format



- SFD sequence
 - It is used to break the preamble pattern and signal the start of the PHR

SFD False Alarm Scenario 1


- Scenario 1: No packet transmission in the air
 - The incoming bits at the receiver might be random
 - False alarm rate
 - Probability that the incoming random noise pattern are exactly matched with pre-defined SFD sequence
 - If false alarm occurs, the receiver starts to recover the PHR and PSDU. => It entails unnecessary energy consumption
 - $R_{\text{false}} = 0.5^n$ where n is the SFD length: doc.030/r0
 - When $n=13$, $R_{\text{false}} = 10^{-4}$: it means that SFD false alarm occurs at every 0.27sec (4 false alarms during 1sec)
 - There is issue how often the false alarm can be allowed per second.

SFD False Alarm Scenario 1

- Scenario 1: No packet transmission in the air
 - Solution for reducing false alarm rate when random input bit is assumed: doc.014/r1
 - In conjunction with preamble pattern (0xAA or 0x55), lower R_{false} value can be obtained due to increased n
 - For example
 - SFD sequence: 0110111101001110
 - Preamble pattern: multiples of 01010101
 - New sequence at the SFD detector
 - 01010101+0110111101001110
 - $n = 24$, $R_{\text{false}} = 6 \times 10^{-8}$ (=1 false alarm for 450 sec)


SFD False Alarm Scenario 2

- Scenario 2: Packet receiving at the receiver
 - The incoming bits at the receiver might be parts of packet (those are not random any more)
 - False alarm rate: probability that SFD detection occurs at the wrong position, e.g., preamble duration



SFD False Alarm Scenario 2

- Scenario 2: Packet receiving at the receiver
 - In this scenario, false alarm rate of 10^{-2} means 1 false alarm per 100 packets




Simulation environment details:
Doc. 877/r0

SFD False Alarm Scenario 2

- Scenario 2: Packet receiving at the receiver
 - For 1% PER, less than 10^{-2} false alarm rate is required
 - Since more than 120dB path loss should be considered in LECIM, the operating SNR will be low in harsh environments
 - Then, the solution for lowering false alarm rate at low SNR is to lengthen the SFD sequence


SFD False Alarm Scenario 2

- Scenario 2: Packet receiving at the receiver
 - Is it possible to use preamble pattern for lengthening the SFD sequence?
 - In preamble duration, the use of preamble pattern on SFD detection does not give any advantage to lower the SFD false alarm rate




SFD False Alarm Scenario 2

- Scenario 2: Packet receiving at the receiver
 - Although 3-octet (0x55+2-octet SFD) is used, the difference in correlator output is same as 2-octet SFD case → no advantage



2-octet SFD sequence



0x55+2-octet SFD sequence

Conclusions

- Two different scenarios are considered for SFD false alarm rate
 - No packet transmission v.s. packet reception
 - Longer SFD sequence can help lowering the false alarm rate
 - During packet reception, the concatenation of preamble pattern on SFD detection is useless
- SFD sequence length
 - In order to satisfy 1% PER performance, 2-octet SFD is not enough at low SNR