Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: [Proposal for IEEE802.15.3e – General Introduction]

Date Submitted: [10 September 2015]

Source: [Ko Togashi⁽¹⁾, Ken Hiraga, Jae Seung Lee, Itaru Maekawa, Makoto Noda,

(representative contributors), all contributors are listed in "Contributors" slide]

Company: [ETRI, JRC, NTT, Sony, Toshiba¹]

Address¹: [1-1-1 Shibaura, Minato-ku, Tokyo 105-8001]

E-Mail¹: [ko.togashi@toshiba.co.jp (all contributors are listed in "Contributors" slide)]

Abstract: This document presents an overview of the full MAC/PHY proposal for HRCP.

Purpose: To propose a full set of specifications for TG 3e.

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributors acknowledge and accept that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Contributors

In alphabetical order

Name	Affiliation	Email
Jae Seung Lee	ETRI	jasonlee@etri.re.kr
Moon-Sik Lee	ETRI	moonsiklee@etri.re.kr
Itaru Maekawa	Japan Radio Corporation	maekawa.itaru@jrc.co.jp
Lee Doohwan	NTT Corporation	lee.doohwan@lab.ntt.co.jp
Ken Hiraga	NTT Corporation	hiraga.ken@lab.ntt.co.jp
Masashi Shimizu	NTT Corporation	masashi.shimizu@upr-net.co.jp
Keitarou Kondou	Sony Corporation	Keitarou.Kondou@jp.sony.com
Hiroyuki Matsumura	Sony Corporation	Hiroyuki.Matsumura@jp.sony.com
Makoto Noda	Sony Corporation	MakotoB.Noda at jp.sony.com
Masashi Shinagawa	Sony Corporation	Masashi.Shinagawa@jp.sony.com
Ko Togashi	Toshiba Corporation	ko.togashi@toshiba.co.jp
Kiyoshi Toshimitsu	Toshiba Corporation	kiyoshi.toshimitsu@toshiba.co.jp

Proposal for IEEE802.15.3e High-Rate Close Proximity System

September 15, 2015

September 2015 doc.: IEEE 15-15-0657-01-003e

Joint Proposal

After numerous discussions among the participant companies, a structure of the proposal acceptable to all parties was arrived at, and it was decided that working on a single, unified proposal was the best way forward to develop the 3e standard in the most effective, efficient and comprehensive manner.

The MAC section is derived from 802.15.3/b/c and contains various modifications and simplifications to optimize operation to the new HRCP (High Rate Close Proximity) mode of communications.

The PHY section is divided into two major co-optional solutions, based on single-carrier modulation and OOK modulation. These two PHY solutions cater to various different usage models but they both share and rely on a single common MAC protocol.

Merits of Close Proximity (Review)

- P2P (Point-to-Point) connectivity is easily implemented
- Touch-based connectivity is easily achieved
 - Quick, simple and intuitive operation for everyone
 - No setup procedures needed to establish connection



Short connection time made possible by:

- → quick link setup
- → quick link release
- → data integrity at MAC level
- Low latency using simple MAC
 - Removal of unnecessary processes not essential for P2P connectivity
 - Required processes are streamlined for dedicated P2P operation
- Robustness against errors and fluctuations
 - No serious throughput degradation nor stability problems

Limiting operation to Close Proximity

- Establish nominal operational coverage
 - Implementation dependent
 - Distance coverage of 10 cm at minimum rate
 - Automatic system switch-on function based on fast setup time under 2 msec.
- Data rate and connection time
 - Maximum PHY SAP rate per 2.16GHz bandwidth shall exceed that of 15.3c
 (ie., more than 5.775 Gbps using 64 QAM)
 - Must satisfy the conditions for maximum connection time while also capable of achieving 100 Gbps using at least one mode.




- ◆ No interference or co-existence issues
 - Because of the close proximity nature of the wireless propagation, there are no interference or co-existence issues.

60 GHz frequency band

Out of the four channels defined for the 60GHz ISM band, channels 1, 2 and 3 should be used for HRCP, either individually, bonded or aggregated (ie., channels 1+3), as these three base channels are allowed by the major regulatory domains (US, Japan, Europe, South Korea).


As of September 2015




Coordination

- ◆ Since the topology is limited to P2P, the system is not a "piconet" but just a P2P structure with just two devices. The coordinator is:
 - Not a PNC but a PPC (P2P Coordinator)
- Redundant processes can be removed to optimize for P2P connectivity:
 - No coordinator handover
 - No child piconet
 - No neighbor piconet
 - No parent piconet
 - No PNC shutdown
 - No parameter changes in system
 - No periodic exchange of management frames

System structure definition



Coordinator definition



Superframe



- No Beacons are sent once connection is established
 - No handover or transfer of the coordinator
 - No new DEV will join (always two)
 - No system parameter modifications
 - Full bandwidth available (at all times)
- No CAP or CTA
 - PPAP (P2P Access Period) only
 - Access to full bandwidth since the communications is P2P and there is no need to assign any time division

Other management aspects



- No information discovery after connection is established
 - Data transfer starts immediately.
- ◆ No dynamic channel selection
 - Default channel is preset to achieve short connection setup.
- ◆ No peer information retrieval and no channel status request
 - Fixed P2P connection reduces connection time.
- ◆ No information announcement to peers and no remote scan
 - No need to transmit since the single peer device remains constant.
- ◆ No stream management
 - Short connection time is optimized for a single, unique transaction.
- ◆ No second exchange in Association procedure
 - Capability negotiation limited to a single exchange to achieve short setup time
- Short Setup time
 - Time from first successful reception of all necessary information from the management frame(s) to completion of association by both devices.
- No Piconet identifiers
 - No exchange of PNID for each session

Data exchange



- ♦ No Carrier Sense (no CSMA)
 - Close proximity P2P will always have full access to entire bandwidth
- No Delayed or Implied ACK
 - Derived from throughput and data integrity considerations
 - Upper layer throughput will be degraded since TX will have to wait for a response
 - Applicable only for isochronous data streams (which are not supported)
- No selective repeat (No Block ACK)
 - Derived from throughput and data integrity considerations
- Data throughput
 - Shall be calculated at the MAC SAP.

Appendix: Evaluation Criteria

doc.:	IEEE	15-15-	0657-	01-003e

PHY criteria		Location
1	Communication distance: Must demonstrate link budget values at a distance of 10 cm based on simulation.	Section 12a
2	Frequency: Shall operate within the 60GHz unlicensed band	Section 12a
3	Interference: Shall be able to operate in dense environments without mutual interference among 3e devices	Section 12a
4	Coexistence: Shall be able to coexist with other systems in the same band when operating without any beamforming technology	Section 5,12a
5	Data Rate: Calculated at the PHY SAP: At least one mode shall be capable of achieving 100 Gbps satisfying the common frequency regulations of US, EU, Korea, and Japan	Section 12a
6	Antenna form factor: The antenna used for satisfying the other PHY criteria shall be small enough for placement and operation inside a mobile device, including smartphones.	Section 12a

MA	MAC criteria	
1	Connection setup time: less than 2 ms	Section 5
2	Definition of "Connection setup time" : time from first successful reception of all necessary information from the management frame(s) to completion of association by both devices.	Section 5
3	P2P: Operation shall be limited to point-to-point connection between two devices only	Section 5
4	No identifiers: Connection setup shall be performed without exchanging network identifiers (PNID) for each session	Section 6
5	NO CSMA: No Listen before Talk (or CSMA) shall be used prior to transmission	Section 5
6	Management frames: No periodic management frames shall be transmitted after completion of association	Section 7
7	Data throughput: Shall be calculated at the MAC SAP	Section 6
8	Error detection and correction: In the presence of random and burst errors, there shall not be serious throughput degradation nor falling into unstable states	Section 7

System criteria		Location
1	Touch action : Bringing the antennas to within about 1 cm shall trigger the two devices to establish connection. Accurate spatial alignment shall not be required.	Section 12a
2	Disconnection: Shall be able to disconnect promptly when devices draw apart beyond 10 cm	Section 12a
3	Efficient design: System shall achieve high throughput and low latency using simple design.	Section 12a
4	Mobile devices should be energy-efficient.	Section 12a

September 2015 doc.: IEEE 15-15-0657- -003e

3e at a glance

Overview

(Colored sections: Areas of modifications)

- 2. References
- 3. Definitions
- 4. Acronyms and abbreviations
- 5. General description → P2P structure, coordination, superframe
- 6. Layer management → MLME, SAP interface
- 7. MAC frame formats → frame types, IE, command types
- 8. MAC functional description → association & disassociation, IFS, PPAP, ACK
- 9. Security
- 10. Security specifications
- 11. PHY specifications for 2.4GHz
- 12. PHY specifications for millimeter wave

12a. PHY specifications for HRCP → general, HRCP-SC, HRCP-OOK

13. Beamforming
Annex A-D