July 2022

doc.: IEEE 802.15-22-0353-00-0thz-Inter-Carrier Interference for IEEE 802.15.3d Multiband Transmission

Project: IEEE P802.15 Working Group for Wireless Speciality Networks (WSN)

Submission Title: Inter-Carrier Interference for IEEE Std 802.15.3d Multiband Transmission

Date Submitted: 11 July 2022

Source: Thomas Kürner TU Braunschweig

Address Schleinitzstr. 22, D-38092 Braunschweig, Germany

Voice:+495313912416, FAX: +495313915192, E-Mail: t.kuerner@tu-bs.de

Re: n/a

Abstract: This document describes a simulation study on potential intercarrier interference when aggregating up to four

channels in IEEE Std 802.15.3d

Purpose: Information of SC THz

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Horizon 2020

National Institute of Information and Communications Techno

Representation of Information and Communications Technology of Information and Communications Technology of Information and Informa



Inter-Carrier Interference for IEEE 802.15.3d Multiband Transmission

Influence of the transmit pulse on the bit error rate

Johannes M. Eckhardt, Christoph Herold, Thomas Kürner Institut für Nachrichtentechnik (IfN) Technische Universität Braunschweig


Multiband Transmission with IEEE 802.15.3d

H2020 ThoR project demonstrates a multiband transmission for wireless backhaul links [1]

IEEE 802.15.3d defines channels with a bandwidth from 2.16 GHz to 69.12 GHz

Transmit power spectrak density (PSD) mask prevents intercarrier interferecen (ICI)

Which transmit pulses comply with the defined transmit spectral mask of IEEE 802.15.3d?




IEEE 802.15.3d channel plan [2] (© 2020 IEEE, reproduced with permission)



Link Level Simulations with SiMoNe

- Link level simulator in SiMoNe [3] was extended by a multi-carrier mode
- Independently configurable subcarriers can be transmitted in parallel





Spectrum of RECT and SINC pulse


2.16 GHz channel, 1.76 GBd symbol rate

rectangular pulse shaping

- High inter-carrier interference
- IEEE 802.15.3d transmit spectral mask in red


sinc pulse shaping

- Pulse duration corresponds to 128 times of the symbol duration
- No practical use






Spectrum of RRC pulse with different roll-off factor α



Spectrum of RRC pulse with different roll-off factor α

 $\alpha > 0.3$ does not comply with the power spectrum masks anymore


How does the transmit pulse affect the bit error rate?





Multiband configuration


- Channel IDs 1-24, 33-44, 49-54, 62-64, 68
- Subcarrier symbol rates 1.76 GBd, 3.52 GBd, 7.04 GBd, 14.08 GBd, 42.24 GBd
- 16-QAM modulation
- No channel coding
- Perfect channel without AWGN
- RRC pulse with different roll-off factors
- 10 Mbit transmitted



Exemplary PSD of CHNL IDs 62-64



Bit error rate from inter-carrier interference





Thomas Kürner| IEEE 802 Plenary | 14 July 2022 | Inter-Carrier Interference for IEEE 802.15.3d Multiband Transmission| 9/13

Bit error rate

ROF / CHNL BW	2.16 GHz	4.32 GHz	8.64 GHz	17.28 GHz	51.84 GHz
0	0	0	0	0	0
0.1	0	0	0	0	0
0.2	0	0	0	0	0
0.3	0	0	0	0	0
0.4	0	0	0	0	0
0.5	$4.15 \cdot 10^{-8}$	$3.31 \cdot 10^{-8}$	$1.64 \cdot 10^{-8}$	0	0
0.6	$2.01 \cdot 10^{-4}$	$1.81 \cdot 10^{-4}$	$1.49 \cdot 10^{-4}$	$7.55 \cdot 10^{-5}$	0
0.7	$3.5 \cdot 10^{-3}$	$3.1 \cdot 10^{-3}$	$2.5 \cdot 10^{-3}$	$1.3 \cdot 10^{-3}$	0
0.8	$1.3 \cdot 10^{-2}$	$1.2 \cdot 10^{-2}$	$9.3 \cdot 10^{-3}$	$4.8 \cdot 10^{-3}$	0
0.9	$2.7 \cdot 10^{-2}$	$2.5 \cdot 10^{-2}$	$2.0 \cdot 10^{-2}$	$1.1 \cdot 10^{-2}$	0
1.0	$4.3 \cdot 10^{-2}$	$4.0 \cdot 10^{-2}$	$3.3 \cdot 10^{-2}$	$2.0 \cdot 10^{-2}$	0



Conclusion


- Transmit spectral mask prevents inter-carrier interference
- Root-raised cosine with roll-off factor < 0.3 agrees with the transmit spectral mask
- Roll-off-factors > 0.4 lead to inter-carrier interference



References

[1] https://thorproject.eu/

- [2] V. Petrov, T. Kürner and I. Hosako, "IEEE 802.15.3d: First Standardization Efforts for Sub-Terahertz Band Communications toward 6G," in IEEE Communications Magazine, vol. 58, no. 11, pp. 28-33, 2020.
- [3] J. M. Eckhardt, C. Herold, B. K. Jung, N. Dreyer and T. Kürner, "Modular link level simulator for the physical layer of beyond 5G wireless communication systems," Radio Science, vol. 57, no. 2, e2021RS007395, 2022.



Thank you for your attention!

ご清聴ありがとうございました


























This project has received funding from Horizon 2020, the European Union's Framework Programme for Research and Innovation, under grant agreement No. 814523. ThoR has also received funding from the National Institute of Information and Communications Technology in Japan (NICT).

Horizon 2020

This project is co-funded by





