Project: IEEE P802.15 Working Group for Wireless Personal Area Networks (WPANs)

Submission Title: Preamble proposal for Long Range SUN-OFDM employing Zadoff-Chu sequences

Date Submitted: July 10, 2023

Source: Henk de Ruijter, Fabrice Portier and Emmanuel Gautier, Silicon

Labs

Address: 400 W Cesar Chavez St, Austin, TX 78701

Abstract: Overview of proposed resolutions


Purpose: Discussion

Notice: This document has been prepared to assist the IEEE P802.15. It is offered as a basis for discussion and is not binding on the contributing individual(s) or organization(s). The material in this document is subject to change in form and content after further study. The contributor(s) reserve(s) the right to add, amend or withdraw material contained herein.

Release: The contributor acknowledges and accepts that this contribution becomes the property of IEEE and may be made publicly available by P802.15.

Introduction:

- A single carrier preamble was presented in 802.15 [1]:
 - Three pre-defined advertiser tones (-12,-2,12). Only one of them is used for a given TX



- The single tone preamble can be sensitive to co-channel interference and frequency selective fading
 - The preamble tone could be blocked by another transmission
- In this presentation a preamble scheme is proposed with improved frequency diversity, providing better tolerance to narrow band interference.

Preamble requirements:

- Tolerant to narrow band interferers
- Detection sensitivity -120 ~ -130 dBm
- Low PAPR (< 2dB)
- Low detection complexity
 - Low power consumption while searching for Preamble
- IP reuse of HW present in SUN-OFDM transceivers

Precoded-OFDM preamble:

- Based on CAZAC sequence
 - CA: Constant Envelope \rightarrow low PAPR
 - ZAC: Zero Autocorrelation \rightarrow good detection properties
 - E.g: generalized ZC (Zadoff-Chu) sequence

 $S_{GZC(N,P,Q,U)}[n] = \exp\left(j\left(P + \frac{2\pi}{N}\frac{Q}{2}n + \frac{2\pi}{N}\frac{U}{2}n^2\right)\right), 0 \le n \le N-1$

- Distinct slope (frequency vs time) can be used suppress detection of other networks (e.g. CSS transmissions)
- Slope is determined by U, N, Fs
- If *N* is prime, DFT of ZC sequence is another ZC sequence
- ZC preambles are used in the 3GPP LTE air interface [2]
 - Combined with an OFDM payload


Precoded-OFDM preamble, example 1:

- Preamble bandwidth: 333 kHz
- Can be divided into two parts
 - STF0 \rightarrow for preamble detection and symbol time synchronization
 - STF1 \rightarrow for synchronization (SFD)
- Normalized Frequency ($\times \pi$ radians/sample) 9.0 $\times 0$ $\times 0$ **S0 S1*** 520kHz Preamble 333kHz Data STF1 **PHR/DATA STF0** 0.5 1.5 2 2.5 3 3.5 1 Samples $\times 10^4$



Precoded-OFDM preamble, example 2:

- Different STF0 and STF1 sequences, could be pre-negotiated to filter out undesired transmissions.
- Besides SFD, ZC can also be used to transmit data:
 - PHR could also be transmitted with ZC sequence (after STF1)
 - DATA could also be transmitted with ZC sequence instead of single carrier OFDM




Extensive reuse of SUN-OFDM IP:





Rx block diagram



Conclusion:

- A low complexity preamble is proposed with:
 - Improved frequency diversity, and hence, tolerant to NB interference
 - Low PAPR for high efficiency PA
 - Reuse of OFDM hardware is possible
 - Estimated detection sensitivity (1% error rate):

Duration @333kHz	Sensitivity (AWGN)
~30 ms	-130dBm
~18 ms	-128dBm
~14 ms	-126dBm
~8 ms	-124dBm

References:

[1] Low data rate extension of the OFDM PHY, IEEE 802.15, DCN: 15-23-0261-02

[2] ETSI TS 136 211 V9.0.0